


## 145.2420CF | 5-Hole Deck Mounted Cascade / Sheet Flow Roman Tub Filler



## **SPECIFICATIONS:**

- Solid Brass construction includes valves DKM.2420
- Spout Projection = 6.1"
- Flow Rate 8 GPM
- Hand Shower Flow Rate = 1.8 GPM @ 60 PSI w/ back flow prevention
- 1/2" NPT Connection
- Diverter Handle control water flow between cascade and hand held

## **STANDARDS:**

ASME A112.18.1 / CSA B125.1

## **Technical Diagram**

0.79in

R20.00mm

0.63in

R16.00mm

